

University of East London - Stratford Campus - New Education Blocks



Client Information

Dean & Dyball, London

Administrated from:	Corrib House (head office)
Form of contract:	JCT Intermediate Form with Design
Contract location:	University of East London - Stratford Campus
Value:	£450,000.00 (one off)
Final value:	£450,000.00
Duration:	February 2008 to November 2008
Sector(s):	Education, Sustainable
Type(s) of work:	New build
Short description:	Facades/Cladding Envelope to new Education Blocks

Works involved - Light Weight Metal Framing to curved Facades & infill areas, insulated with Rockwool Insulation, then clad in cement particle board ready for Marley Eternit Cladding System. We installed Marley Eternit Cladding System to the curved facades off Cherry Pickers.

The Eternit Panels were mainly factory cut with the curved sections formed on site to a very high standard by our trained personnel.

The Framing system was installed to Curves and was a intricate and highly detailed operation to form the curves to the building as required by the Architect.

Project Team

Responsible Director; Duncan Brown

Project Manager; Jeff Pearce

Site Manager; Dominic Devine

